

KINDERGARTEN

June 25, 2012

I. PROGRAM REQUIREMENTS

Refer to the project-specific Schedule of Spaces for student stations, square footage, and any requirements that may differ from the prototype requirements listed below:

- 6 Classrooms
- 1 Teacher Planning Area (shared with Primary)
- 6 Student Toilet Rooms
- 3 Material Storage Rooms

II. PROGRAM FURNITURE AND EQUIPMENT

Refer to the Furniture and Equipment List for Owner-provided furniture and equipment.

III. SPECIFIC CONSIDERATIONS

1. Heating/Ventilation/Air Conditioning

Standard, refer to the General Design Requirements section.

2. Acoustical

Standard, refer to the General Design Requirements section.

3. Floor

Standard, refer to the General Design Requirements section.

4. Walls

Standard, refer to the General Design Requirements section.

5. Ceiling

Standard, refer to the General Design Requirements section.

6. Lighting

Standard, refer to the General Design Requirements section.

7. Windows

Standard, refer to the General Design Requirements section.

8. Doors

Provide an opening (no door) between each pair of adjacent Classrooms.

9. Water

Classrooms (each)

Provide one (1) sink with hot and cold water, located near the Student Toilet Room.

Provide one (1) electric water cooler for each pair of Classrooms, mounted 30" above the floor to the bubbler, located near the Student Toilet Rooms.

Student Toilet Rooms (each)

Provide one (1) toilet and one (1) wall-mounted lavatory with cold water.

10. Communications

Classrooms (each)

Provide a clock, intercom speaker and intercom handset in accordance with SDHC standards.

Provide two (2) AV speakers, mounted on each side of the markerboard.

Provide data and AV connections and associated power outlets for the projector, in accordance with the General Design Requirements section and SDHC standards.

Teacher Planning Area

Provide a clock and intercom speaker in accordance with SDHC standards.

Provide voice/data and associated power outlets, in accordance with the General Design Requirements section and SDHC standards.

11. Electrical

Provide two (2) duplex outlets above the countertop in each Classroom.

Provide a disconnect switch for the range, located near the range in each Classroom.

12. Gas and Air

Not applicable

13. Safety

Provide a fire extinguisher in a recessed cabinet, located near the range.

14. Fencing

Not applicable

15. Service Drives

Not applicable

16. Parking

Not applicable

17. Contractor-Provided Equipment and Casework

Classrooms (each)

Provide six (6) linear feet of base and wall cabinet to include the sink and one (1) adjacent bank of graduated drawers, countertop to be 30" above the floor.

Provide three (3) linear feet of base and wall cabinet to include the under-counter refrigerator (listed below), countertop to be 36" above the floor. The range (listed below) is to be located adjacent to this base cabinet.

Provide one (1) general storage cabinet, see SDHC standard detail.

Provide one (1) range with oven and hood.

Provide one (1) under-counter type refrigerator with freezer compartment.

Material Storage Rooms (each)

Provide material storage shelving, see SDHC standard detail.

18. Contractor-Provided Instructional Aids

Classrooms (each)

Provide a 12' wide x 5' high markerboard with a 4' wide x 5' high tackboard on one (1) side and a 1' high continuous tack strip above, bottom to be mounted 24" above the floor.

On an adjacent wall provide a self-healing tackable wall surface which extends from the top of the base to the ceiling and covers the entire wall from corner to corner.

Provide a 4' wide x 4' high tackboard in the Teacher Planning Area.

Install an owner-provided projector and mounting bracket, centered on the wall over the markerboard.

19. Other Considerations

Kindergarten Classrooms are to be arranged in pairs.

SPACE RELATIONSHIPS

