

**EXCEPTIONAL STUDENT EDUCATION:  
SPECIFIC LEARNING DISABLED CLASSROOM (SLD)**

September 30, 2010

**I. PROGRAM REQUIREMENTS**

Refer to the project-specific Schedule of Spaces for student stations, square footage, and for any requirements that may differ from the prototype requirements listed below:

- 1 Classroom

**II. PROGRAM FURNITURE AND EQUIPMENT**

Refer to the Furniture and Equipment List for Owner-provided furniture and equipment.

**III. SPECIAL CONSIDERATIONS**

**1. Heating/Ventilation/Air Conditioning**

Standard, refer to the General Design Requirements Section.

**2. Acoustical**

Standard, refer to the General Design Requirements Section.

**3. Floor**

Standard, refer to the General Design Requirements Section.

**4. Walls**

Standard, refer to the General Design Requirements Section.

**5. Ceiling**

Standard, refer to the General Design Requirements Section.

**6. Lighting**

Standard, refer to the General Design Requirements Section.

**7. Windows**

Standard, refer to the General Design Requirements Section.

**8. Doors**

Standard, refer to the General Design Requirements Section.

**9. Water**

Not applicable

**10. Communications**

Provide a clock, speaker and intercom handset in the Classroom.

Provide a data outlet with adjacent power outlet in the Classroom, in accordance with the General Design Requirements section and SDHC standards.

Provide a TV bracket with DVD/VCR bracket, CCTV jack, and adjacent power outlet in the Classroom, in accordance with SDHC standards.

**11. Electrical**

Standard, refer to the General Design Requirements Section.

**12. Gas and Air**

Not applicable

**13. Safety**

Standard, refer to the General Design Requirements Section.

**14. Fencing**

Not applicable

**15. Service Drives**

Not applicable

**16. Parking**

Not applicable

**17. Contractor-Provided Equipment and Casework**

Classroom

Provide twelve (12) linear feet of lockable base and wall cabinets, to include one (1) bank of lockable graduated drawers, countertop to be 36" above the floor.

Provide two (2) lockable storage cabinets, see standard detail.

**18. Contractor-Provided Instructional Aids**

Classroom

Provide a 12' wide x 4' high markerboard with a 4' wide x 4' high tackboard on one (1) side, bottom to be mounted 36" above the floor.

Provide a wall-mounted audio-visual projection screen, approximately 70" x 70", centered over the markerboard.

**19. Other Considerations**

Not applicable

# SPACE RELATIONSHIPS

