

**EXCEPTIONAL STUDENT EDUCATION:  
EH/SLD RESOURCE ROOMS**

September 30, 2010

**I. PROGRAM REQUIREMENTS**

Refer to the project-specific Schedule of Spaces for student stations, square footage, and for any requirements that may differ from the prototype requirements listed below:

4 EH/SLD Resource Rooms

**II. PROGRAM FURNITURE AND EQUIPMENT**

Refer to the Furniture and Equipment List for Owner-provided furniture and equipment.

**III. SPECIAL CONSIDERATIONS**

**1. Heating/Ventilation/Air Conditioning**

Standard, refer to the General Design Requirements Section.

**2. Acoustical**

Standard, refer to the General Design Requirements Section.

**3. Floor**

Standard, refer to the General Design Requirements Section.

**4. Walls**

Standard, refer to the General Design Requirements Section.

**5. Ceiling**

Standard, refer to the General Design Requirements Section.

**6. Lighting**

Standard, refer to the General Design Requirements Section.

**7. Windows**

Standard, refer to the General Design Requirements Section.

**8. Doors**

Standard, refer to the General Design Requirements Section.

**9. Water**

Not applicable

**10. Communications**

Provide a clock, speaker and intercom handset in each Resource Room.

Provide a data outlet with adjacent power outlet in each Resource Room, in accordance with the General Design Requirements section and SDHC standards.

Provide a TV bracket with DVD/VCR bracket, CCTV jack, and adjacent power outlet in each Resource Room, in accordance with SDHC standards.

**11. Electrical**

Standard, refer to the General Design Requirements Section.

**12. Gas and Air**

Not applicable

**13. Safety**

Standard, refer to the General Design Requirements Section.

**14. Fencing**

Not applicable

**15. Service Drives**

Not applicable

**16. Parking**

Not applicable

**17. Contractor-Provided Equipment and Casework**

Resource Rooms (each)

Provide twelve (12) linear feet of lockable base and wall cabinets, to include one (1) bank of lockable graduated drawers, countertop to be 36" above the floor.

Provide two (2) general storage cabinets, see SDHC detail.

**18. Contractor-Provided Instructional Aids**

Resource Rooms (each)

Provide a 12' wide x 4' high markerboard with a 4' wide x 4' high tackboard on one (1) side, bottom to be mounted 36" above the floor.

Provide a wall-mounted audio-visual projection screen, approximately 70" x 70", centered over the markerboard.

**19. Other Considerations**

Locate an EH/SLD Resource Room in each of the 9<sup>th</sup>, 10<sup>th</sup>, 11<sup>th</sup> and 12<sup>th</sup> Grade areas.

# SPACE RELATIONSHIPS

