

WORK EXPERIENCE STUDIES

September 30, 2010

I. PROGRAM REQUIREMENTS

Refer to the project-specific Schedule of Spaces for student stations, square footage, and for any requirements that may differ from the prototype requirements listed below:

- 1 Laboratory
- 1 Teacher Planning/Material Storage Rm.

II. PROGRAM FURNITURE AND EQUIPMENT

Refer to the Furniture and Equipment List for Owner-provided furniture and equipment.

III. SPECIAL CONSIDERATIONS

1. Heating/Ventilation/Air Conditioning

Standard, in accordance with the General Design Requirements section.

2. Acoustical

Standard, in accordance with the General Design Requirements section.

3. Floor

Standard, in accordance with the General Design Requirements section.

4. Walls

Standard, in accordance with the General Design Requirements section.

5. Ceiling

Standard, in accordance with the General Design Requirements section.

6. Lighting

Standard, in accordance with the General Design Requirements section.

7. Windows

Standard, in accordance with the General Design Requirements section.

8. Doors

Provide a half-glass door from the Teacher Planning/Material Storage Room into the Laboratory.

9. Water

Not applicable

10. Communications

Provide a clock, speaker and intercom handset in the Laboratory and Teacher Planning/
Material Storage Room.

Provide a data outlet with adjacent power outlet in the Laboratory, in accordance with the
General Design Requirements section and SDHC standards.

Provide a voice/data outlet with adjacent power outlet in the Laboratory and Teacher
Planning/Material Storage Room, in accordance SDHC standards.

Provide a TV bracket with DVD/VCR bracket, CCTV jack, and adjacent power outlet in the
Laboratory, in accordance with SDHC standards.

11. Electrical

Standard, in accordance with the General Design Requirements section.

12. Gas and Air

Not Applicable

13. Safety

Standard, in accordance with the General Design Requirements section.

14. Fencing

Not Applicable

15. Service Drives

Not Applicable

16. Parking

Not Applicable

17. Contractor-Provided Equipment and Casework

Laboratory

Provide nine (9) linear feet of base and wall cabinets, to include one (1) bank of graduated
drawers, countertop to be 36" above the floor.

18. Contractor-Provided Instructional Aids

Laboratory

Provide a 12' wide x 4' high markerboard with a 4' wide x 4' high tackboard on one (1) side,
bottom to be mounted 36" above the floor.

Provide a wall-mounted audio-visual projection screen, approximately 70" x 70", centered
over the markerboard.

19. **Other Considerations**

Not Applicable

SPACE RELATIONSHIPS

