

# **CRIMINAL JUSTICE ASSISTING**

September 30, 2010

## **I. PROGRAM REQUIREMENTS**

Refer to the project-specific Schedule of Spaces for student stations, square footage, and for any requirements that may differ from the prototype requirements listed below:

- 1 Laboratory
- 1 Material Storage Room

## **II. PROGRAM FURNITURE AND EQUIPMENT**

Refer to the Furniture and Equipment List for Owner-provided furniture and equipment.

## **III. SPECIAL CONSIDERATIONS**

### **1. Heating/Ventilation/Air Conditioning**

Standard, in accordance with the General Design Requirements section.

### **2. Acoustical**

Standard, in accordance with the General Design Requirements section.

### **3. Floor**

Standard, in accordance with the General Design Requirements section.

### **4. Walls**

Standard, in accordance with the General Design Requirements section.

### **5. Ceiling**

Standard, in accordance with the General Design Requirements section.

### **6. Lighting**

Standard, in accordance with the General Design Requirements section.

### **7. Windows**

Standard, in accordance with the General Design Requirements section.

### **8. Doors**

Standard, in accordance with the General Design Requirements section.

### **9. Water**

Provide one (1) sink with cold water in the Laboratory.

**10. Communications**

Provide a clock, speaker and intercom handset in the Laboratory.

Provide a data outlet with adjacent power outlet in the Laboratory, in accordance with the General Design Requirements section and SDHC standards.

Provide a TV bracket with DVD/VCR bracket, CCTV jack, and adjacent power outlet in the Laboratory, in accordance with SDHC standards.

**11. Electrical**

Standard, in accordance with the General Design Requirements section.

**12. Gas and Air**

Not applicable

**13. Safety**

Standard, in accordance with the General Design Requirements section.

**14. Fencing**

Not applicable

**15. Service Drives**

Not applicable

**16. Parking**

Not applicable

**17. Contractor-Provided Equipment and Casework**

Laboratory

Provide nine (9) linear feet of base and wall cabinets, to include the sink and one (1) adjacent bank of graduated drawers, countertop to be 36" above the floor.

Provide twenty (20) lockers, 12" wide x 15" deep x 30" high.

**18. Contractor-Provided Instructional Aids**

Laboratory

Provide a 12' wide x 4' high markerboard with a 4' wide x 4' high tackboard on one (1) side, bottom to be mounted 36" above the floor.

Provide a wall-mounted audio-visual projection screen, approximately 70" x 70", centered over the markerboard.

**19. Other Considerations**

Not applicable

# SPACE RELATIONSHIPS

